

Genoa Community Church

182 Nixon Street, Genoa, Nevada 89411

Exterior Painting Project

All estimates must include labor and all materials. The project is to be completed on or before June 30, 2024.

- The entire building must be pressure washed
- A detailed prep of the exterior, including the covering of all windows, concrete, roof shingles, etc.
- Caulk any open, cracked or split joints
- All wood rot or damaged wood must be identified and replaced prior to painting
- All exterior wood, including the handrails front and side of building, must be scrapped as needed. This is to include the fascia, soffit and entire exterior of the building
- A quality primer must be applied to all wood as necessary
- All exterior doors must be sanded and prepped to be sprayed with an airless sprayer with 2 coats of the highest quality exterior paint (Sherwin-Williams "Emerald" or equivalent)
- The exterior body and trim will then be sprayed and/or rolled with 2 coats of the same quality paint to fully cure and be applied to all crevices of the exterior body
- All gutters will be sanded and sprayed with a factory finish
- Warranty of work must be clearly documented on quote