



TEMPORARY COVER

NOTES:

1. IN ALL AREAS, COVERS SHALL BE SET 1/4" BELOW FINISHED GRADE UNLESS OTHERWISE NOTED.
2. SOLID, GASKETED MANHOLE LIDS WITH AN INSET GASKET EITHER IN THE FRAME OR THE COVER SHALL BE PROVIDED IN ALL FLOOD PLAIN AREAS AND OTHER AREAS AS REQUIRED BY THE UTILITY.

NO.	REVISION	DATE	STANDARD DETAIL FOR PUBLIC WORKS CONSTRUCTION	SECTION: DOUGLAS COUNTY
			TEMPORARY COVER	DATE: JULY 2017
				DWG: A13