



NOTES:

1. CONCRETE SHALL BE FIBER REINFORCED 4000 PSI AT 28 DAYS MIX.
2. CONTRACTOR MAY RAISE LIDS BEFORE OR AFTER OVERLAY AT HIS OPTION.
3. IF NEW BARREL SECTION IS ADDED ALL WORK SHALL CONFORM TO SANITARY SEWER MANHOLE DETAIL C03.
4. CONTRACTOR SHALL MAINTAIN MANHOLE AND SEWER LINES FREE OF DEBRIS AT ALL TIMES.
5. GRADE RINGS SHALL BE PRECAST CONCRETE OR HDPE LADTECH INSTALLED PER MANUFACTURER'S SPECIFICATIONS. WOOD SHIMS ARE NOT ALLOWED WITH LADTECH SYSTEMS.
6. VACUUM TESTING NOT REQUIRED ON EXISTING MANHOLES.

NO.			REVISION			DATE			STANDARD DETAIL FOR PUBLIC WORKS CONSTRUCTION			SECTION: DOUGLAS COUNTY		
<h1 style="margin: 0;">SANITARY SEWER MANHOLE RAISING</h1>									DATE:			JULY 2017		
									DWG:			C05		