


PLAN VIEW



ELEVATION VIEW

(B)30 INCHES MIN. PIPE DEPTH. USE TWO FULL TURNS OF TEFLON TAPE ON ALL THREADED JOINTS.

SEE NOTES ON PAGE 2

PAGE 1 OF 2

			, (302 MBET (11)	В В	17
			ASSEMBLY (RP)	DWC•	
			BACKFLOW PREVENTION	DATE: JULY	2017
				DOUGLAS	COUNTY
NO.	REVISION	DATE	SIMILATION DETAIL FOR FOREIGN WORKS COMSTROOTION	SECTION:	

NOTES:

- 1. RP MUST BE ABOVE GRADE.
- 2. FREEZE PROTECTION (INSULATED ABOVE GROUND VAULT OR HOT BOX AND REDUNDANT HEAT TAPE) IS REQUIRED.
- 3. AN ABOVE GROUND VAULT (HOT BOX OR EQUIVALENT) MUST BE SIZED TO PROVIDE CLEARANCES SHOWN IN PLAN VIEW. A SPRING LOADED LID IS REQUIRED.
- 4. A HOT BOX LID MUST SWING CLEAR OF BACKFLOW PREVENTION ASSEMBLY TO PROVIDE CLEARANCES IN PLAN VIEW.
- 5. STOP AND WASTE VALVES MUST NOT BE USED BETWEEN THE METER AND THE BACKFLOW PREVENTION ASSEMBLY.
- 6. ABOVE GROUND VAULTS AND HOT BOX MUST PROVIDE ADEQUATELY SIZED DAYLIGHT DRAINS AT PAD LEVEL FOR DRAINAGE.
- 7. ELECTRICAL SUPPLY SOCKETS, IF REQUIRED, MUST BE AWAY FROM WATER RELIEF PORT AND TESTCOCKS, AND GFCI PROTECTED.
- 8. THE BACKFLOW PREVENTION ASSEMBLY DEVICE MUST BE VISUALLY INSPECTED BY A CALIFORNIA / NEVADA AWWA OR ABPA CERTIFIED BACKFLOW TESTER AT THE TIME OF INSTALLATION, YEARLY THEREAFTER, AND AFTER REPAIRS, WITH THE RESULTS SENT TO THE WATER UTILITY.
- 9. NO OUTLET TEE, TAP OR CONNECTION SHALL BE INSTALLED BETWEEN SERVICE CONNECTION AND BACKFLOW PREVENTION ASSEMBLY.
- 10. REFER TO RELIEF VALVE DISCHARGE RATE SO THAT ADEQUATE DRAINAGE CAN BE INSTALLED.
- 11. SUPPORTS REQUIRED FOR ASSEMBLIES 2.5" AND LARGER.
- 12. INDOOR INSTALLATION OF BACKFLOW PREVENTION ASSEMBLIES (RP's) SHALL MEET INSTALLATION CLEARANCES OF NAC 445A.67235(6).

PAGE 2 OF 2

			ASSEMBET (KI)	B17
			ASSEMBLY (RP)	DWG: DAT
			BACKFLOW PREVENTION	DATE: JULY 2017
			I DACIZELONA DDENZENTION	DOUGLAS COUNTY
NO.	REVISION	DATE	STATISTICS DETAIL FOR FOREIGN WORKS CONSTRUCTION	SECTION: